



Asphalt Mixing Plant



Concrete Mixing Plant



HZS120 混凝土搅拌站标准配置

HZS120 Concrete Batching Plant

序号 Number	名称 Name		规格 Specification	数量 Quantity	单位 Unit
1	主站结构 Main Structure	下部立柱 Downside Vertical Post		1	套 set
		搅拌层平台 Mixing Platform		1	套 set
		上部排架 Upside Frame Bent		1	套 set
		配料层平台 Batching System Platform		1	套 set
		进料层屋架 Charging layer frame		1	套 set
		外围骨架 Frame work		1	套 set
		梯子、小平台、栏杆 Ladder, platform, Guardrail		1	套 set
2	搅拌主机	双卧轴强制式搅拌机 Twin-shaft concrete mixer	MAO2000	1	套 set
	驱动电机		2X37KW	1	台 set
	减速机 Reducer			1	台 set
	注油泵 Oiling Pump			1	台 set
	自动注油装置 Automatic oiling device			1	台 set
3	骨料称量装置 PLD3200 四仓 Aggregate weighing system PLD32004	骨料仓 Aggregate Bins		1	套 set
		弧门 Arc Door		8	套 set
		称量斗 Weighing Hopper	2000KG	4	套 set
		气缸 Cylinder		10	套 set
		振动器 Vibrator	MVE100/3	4	只 pieces
4	水平皮带机	电动滚筒 Electric Roller	11KW	1	台 set
		输送带 Conveyor Belt	B=800 V=2M/S	1	条 pieces
		弹簧清扫器 Spring Sweeper		1	套 set
		空段清扫器 Sweeper		1	套 set
		托辊 Roller	槽型 Groove Profile		



Asphalt Mixing Plant



Concrete Mixing Plant



		托辊 Roller	槽型调心 Groove Profile		
		托辊 Roller	平行 Parallel		
		托辊 Roller	下平行调心 Parallel		
		螺旋拉紧装置 Screw tension device		1	套 set
		改向滚筒 Roller	Φ500mm	1	个 pieces
		机架及急停装置 Chassis and scrambling device		1	套 set
5	上料皮带机	悬挂减速机 Reducer (Suspended type)	包胶 37KW	1	台 set
		输送带 Conveyor Belt	B=800mm V=2.5M/S	1	条 pieces
		弹簧清扫器 Spring Sweeper		1	套 set
		空段清扫器 Sweeper		1	套 set
		改向滚筒 Roller	Φ500mm	1	套 set
		托辊 Roller	槽型 Groove Profile		
		托辊 Roller	槽型调心 Groove Profile		
		托辊 Roller	平行 Parallel		
		托辊 Roller	下平行调心 Parallel		
		导料槽		1	套 set
		垂直拉紧装置 Vertical tension device		1	套 set
		机架及急停装置 Chassis and scrambling device		1	套 set
6	卸料装置	搅拌机盖 The cover of mixer		1	套 set
		骨料预存斗(内置门) Aggregate store bucket	3m3	1	套 set
		气缸 Cylinder	2- φ100	2	只 pieces
7	主站除尘 Main dust removal system			1	台 set



Asphalt Mixing Plant



Concrete Mixing Plant



8	出料斗 Discharging Bucket	带耐磨衬板 within wear resistant scale board		1	套 set
9	水泥称量装置 Cement Weighing System	水泥计量斗及支架 cement weighing bucket and support	1200KG; ±1%	1	套 set
		气动蝶阀 Pneumatic butterfly valve	SIC300	1	套 set
		传感器悬挂装置 the suspension device for sensor		3	套 set
10	粉煤灰称量装置 Fly ash weighing system	粉煤灰计量斗及支架 Fly ash weighing bucket and support	400KG; ±1%	1	套 set
		气动蝶阀 Pneumatic butterfly valve	SIC300	1	套 set
		传感器悬挂装置 the suspension device for sensor		3	套 set
11	水称量装置 Water weighing system	水泵 water pump	GSL65	1	台 set
		气动蝶阀 Pneumatic butterfly valve	Φ150mm	1	套 set
		水计量斗及支架 water weighing bucket and support	400KG; ±1%	1	套 set
		上水管路、阀门 water piping system, valve	Φ50mm	1	套 set
12	外加剂称量装置 Additive weighing system	耐腐蚀泵 corrosion resistance water	GSH25	2	套 set
		气动球阀（铜） pneumatic ball valve(copper)		1	套 set
		计量斗（不锈钢） weighing bucket (stainless steel)	30KG ±1%	1	套 set
		外加剂管路、阀门 additive piping system, valve		2	套 set
13	气路系统	空压机 air compressor		1	台 set
		电磁气阀 Solenoid Valve			



Asphalt Mixing Plant



Concrete Mixing Plant



		油雾器、分水滤气器 Air Lubricator, water-separating gas filter			
		管道、阀门 pipeline, valve		1	套 set
		储气罐 gasholder	0.6 m3	1	个 pieces
14	螺旋给料装置 Screw conveyor feeding device	螺旋注油装置		4	套 set
		螺旋机支架, 钢丝绳及附件 Screw conveyor support, steel wire rope and accessory		4	套 set
		手动蝶阀及附件 Manual butterfly valve		4	套 set
15	主站外围 (50mm 夹心板) outside structure for concrete batching plant(50mm sandwich panel)			1	套 set
16	微机控制系统 Control System	工业控制计算机 Industrial control computer		1	套 set
		显示器 monitor		1	台 pieces
		放大器 Amplifier	BSA--5		
		I/O 板、A/O 板 I/O board, A/O board	DB--16R		
		抗干扰隔离系统 anti-interference isolation system		1	套 set
		操作按钮 operation button			
		传感器 Sensor		11	套 set
		中间继电器 intermediate relay			
		打印机 printer	中英文 Chinese and English	1	台 pieces
		接触器 contactor			
		热继电器 Thermal relay			
		仪表 instrument			
强电控制柜 High voltage control cabinet		1	台 pieces		



Asphalt Mixing Plant



Concrete Mixing Plant



		操作台 Operation platform		1	台 pieces
		楼内电线、电缆 Cable			
		照明箱/灯具 Lighting			
		应用控制与管理软件 Application Control and management software		1	套 set
		分线盒 Branch box			
		监视器（二头一尾） Monitor	彩色 color	1	套 set
		远程故障诊断 Dust collector		1	套 set
		仓顶除尘（含破拱装置） Dust collector		4	套 set
Total Price EXW166,670 US DOLLAR: ONE HUNDRED AND SIXTY SIX THOUSAND SIX HUNDRED SEVENTY ONLY					
客户选配件 For Customer Choice					
17	控制房 Control Room		2.3m*2.0m*2.0m Leg Height 3m	1	间 Pieces
18	水泥仓 Cement Silo		50T/100T		个 Pieces
19	螺旋输送 Screw Conveyor		LSY219/LSY273mm		根 Pieces